



SCHEDULE OF ITEMS			
ITEM NO.	DESCRIPTION	ITEM NO.	DESCRIPTION
1 & 2	REFER TO DRAWING 17	7	SPACER 3 x PIPE DIAMETER
3	ISOLATING VALVE. IF BUTTERFLY VALVE TO BE GEAR SHUT TYPE	8	RESILIENT SEATED ISOLATING VALVE. IF BUTTERFLY VALVE TO BE GEAR SHUT TYPE
4	DIRT BOX WATER CORPORATION SUPPLIED	9	STRAINER TO CONFORM TO BACKFLOW PREVENTION DEVICE MANUFACTURER'S REQUIREMENTS
5	SPACER 5 x PIPE DIAMETER		
6	APPROVED WATER CORPORATION SUPPLIED WATER METER	10	HIGH / MEDIUM TESTABLE BACKFLOW PREVENTION DEVICE NOTE: MIN HEIGHT 300mm TO DISCHARGE PORT
SEE GENERAL NOTES FOR FURTHER INFORMATION			

**GENERAL NOTES:**

A. Meters 50mm and above to be supported independent of pipework

B. No connection permitted between water meter and backflow device

C. Water corporation is responsible for maintenance to the outlet of the main water meter

DRAWING NUMBER:

7

SCALE:

NOT TO SCALE

DATE:

DECEMBER 2021

80mm+ GENERAL WATER SERVICE  
MEDIUM / HIGH HAZARD  
RESIDENTIAL / COMMERCIAL / INDUSTRIAL  
TYPICAL ARRANGEMENT

