



**Notes:**

- Where the Containment backflow prevention device used is an RPZD, Maintain Min 300mm from the vent to the ground.
- Assembly max height by approval 1.50m.
- Min 6mm annular clearance around pipes where passing through concrete bases.

DRAWING NUMBER:

20

SCALE:

NOT TO SCALE

DATE:

AUGUST 2014

MINIMUM CLEARANCES FOR METER ASSEMBLIES IN CONFINED SPACES

